

# **Heavy Duty Machine Room Less Elevator DESIGN GUIDELINES**

Approved May 2006

**APTA Rail Transit Standards Fixed Structures Inspection and Maintenance  
Committee**

Approved May, 2006

**APTA Rail Transit Standards Task Force**

Authorized June 10, 2006

**APTA Rail Transit Standards Policy Committee**

## INTRODUCTION

This design guideline is the result of the combined efforts of the members of the APTA Elevators and Escalators Technical Forum over the past several years. Membership of the Technical Forum includes Transportation systems, consultants, and elevator and escalator component manufacturers. The objective is to address the specific heavy duty elevator needs of North American Transportation Systems. It is intended as a guideline of technical provisions for the design and construction of elevators which can provide safe, reliable service in the harsh, heavy usage, high abuse environment of Transportation systems.

The newest trend in elevator technology is the Machine-Room-Less elevator (MRL). This technology is being developed by all of the major elevator manufacturers and is installed in thousands of locations throughout the world, including the United States. This design guideline is intended to outline appropriate transit design guidelines for this new technology.

This design guideline is not intended to be a 100%, procurement ready technical specification for all Transportation systems. Each Owner may find it necessary to make changes to suit their specific needs. However, the stringent provisions are the result of the members combined experiences and, in general, reflect Transportation requirements and the need for improved safety and reliability. There are also “comments” and “Notes to specifier” in the text to guide the user in preparation of a procurement specification document.

It is expected that some manufactures will be quick to tell us that these requirements will “add to the cost of the procurement”. We all know, from past experience, the high life cycle maintenance costs associated with the manufacturer’s “standard” product when used in a Transportation environment. Paying “more up front” will be more than compensated for by the overall reduced life cycle costs.

The working group has established these guidelines for traction elevators. They can be used at any rise, including those within the low rise elevator guidelines already established by APTA.

To that end, as with the recently adopted Heavy Duty low rise elevator design guidelines, this Working Group recommends increasing the capacity of the elevators above and beyond that of the ASME A17.1 code required minimums. Table 1 shows the APTA rated minimum load recommendations above that of ASME A17.1 below should be incorporated into the design decisions for all elevators in transportation applications were recommended in the guidelines..

Table 1- Elevator Platform Size vs. Rate Load changes

Platform Width (Ft)	Platform Front to Back (Ft.)	Inside net platform area.(Ft^2)	A17.1 Maximum inside net platform Area (Ft^2)	A17.1 Rated Min.	A17.1 Rated Nominal (Lbs.)	APTA Rated (Lbs.) @ 1.5 over A17.1 minimum
6.00	5.00	24.08	24.2	1993	2000	3000
7.00	5.00	28.33	29.1	2425	2500	3750
7.00	5.50	31.67	33.7	2781	3000	4500
7.00	6.17	36.11	38	3278	3500	5250
8.00	6.17	41.53	42.2	3920	4000	6000
6.00	8.83	45.81	46.2	4455	4500	6750
6.00	9.38	48.88	50	4853	5000	7500

Be sure to coordinate design of elevators with all applicable disciplines affected. This can include architectural, electrical, structural, HVAC as well as fire/life/safety designers.

The use of this guideline will provide improved availability and reliability of transportation elevators and, most importantly, will improve customer safety, satisfaction, and convenience. The results can only be an increase in the public's confidence in the Transportation system's ability to meet their needs, and thus, an increase in ridership.

# HEAVY-DUTY, TRANSPORTATION SYSTEM

## PART I GENERAL

### 1.01 GENERAL DESCRIPTION:

- A. This provides design guidelines for the fabrication, installation, and testing of MRL elevators.

### 1.02 DEFINITIONS:

- A. Heavy duty elevator: An elevator designed specifically for the harsh environment and duty load cycles common to transportation system usage.
- B. Elevator - a hoisting and lowering mechanism, equipped with a car or platform, which moves in guide rails or racks and serves two or more landings and is classified by the following:
  - a. Elevator, freight - an elevator used primarily for carrying freight and on which only the operator and the persons necessary for unloading and loading the freight are permitted to ride.
  - b. Elevator, passenger - an elevator used primarily to carry persons other than the operator and persons necessary for loading and unloading.
  - c. Elevator, insert A17.1 definition for MRL.
- C. Contractor: The General Contractor.
- D. Installer: The responsible party who installs the elevator.
- E. OEM: Original Equipment Manufacturer.
- F. Owner: The owner in control of the facility.
- G. Dwell time: The period of time the elevator is at a landing while the doors open, passengers transfer and doors close.
- H. Substantial completion: The point at which the elevator is ready for use, whether the site is finished or not. This is where the jurisdictional inspection usually takes place.
- I. Final Acceptance: The point at which the owner accepts the elevator project as being complete including all submittal requirements. This may be a different point in time than substantial completion.
- J. Interim Maintenance: Maintenance from the point of substantial completion, but prior to Revenue Service.
- K. Beneficial Use: When the elevator is placed into service, may be prior to the site

- being ready for public use.
- L. Revenue Service: The station or facility opening date.
  - M. Notice to Proceed (NTP): within this document shall mean the date which the elevator installer is notified to proceed with the project.
  - N. Authority Having Jurisdiction (AHJ): as defined by ASME A17.1.

### 1.03 TEMPORARY AND PERMANENT ELECTRICAL POWER SERVICES:

- A. Temporary power for installation shall be made available to Installer at the time of the installation. Permanent power shall be made available for testing. All power shall be provided at no cost to Installer.

Note to specifier: close coordination with the electrical engineer is recommended to provide the proper power supply for a given installation. Additionally, coordination of power for HVAC, smoke and heat detectors, pit lighting, outlets and sump pumps is required by the electrical designer.

- B. For the elevator drive systems: 208, 220 or 480 volts, 3 phase, 3 wire, 60 Hertz terminating in a disconnect switch within sight of the controller.
- C. For lighting and GFCI receptacles: 120 volts, 1 phase, 3 wire, 60 Hertz terminating at the elevator controller location.
- D. Separate disconnect for cab lighting and wiring to cab.
- E. Separate service for sill heaters where required.

### 1.04 APPLICABLE CODES, STANDARDS, ORGANIZATIONS AND PUBLICATIONS:

Elevator designs and installations shall be of the heavy duty type, and shall comply with the following:

- A. American National Standards Institute (ANSI)
  - 1. ASME A17.1, A17.2.3, A17.5 applicable edition
  - 2. ASME A17.1S-2005 (supplement to ASME A17.1-2004)

Note to specifier: you must identify which edition of ASME A17.1 is applicable for your jurisdiction as different editions may affect procurement and installation. Some jurisdictions may not have adopted A17.1S-2005, but will use that addendum to justify a variance.

- B. Canadian Standards Association, CSA B44
- C. National Fire Protection Association (NFPA)
  - 1. NFPA No. 130, "Fixed Guideway Transit and Passenger Rail Systems"
  - 2. ANSI C1, National Electric Code (NFPA 70)
- D. Americans with Disabilities Act Accessibility Guidelines (ADAAG)
- E. IEEE 519 Standard Practices and Requirements for Harmonic Control in Electrical Power Systems
- F. Canadian Welding Bureau (CWB)
- G. American Welding Society (AWS)
- H. American Society of Testing and Material (ASTM)
- I. International Standards Organization, ISO 281/I-1997
- J. American Federation of Bearing Manufacturers Association, AFBMA, Std. 9 and 11
- K. Occupational Safety & Health Act (OSHA)
- L. Any additional requirements imposed by local agencies shall be incorporated into elevator installations.
- M. In case of a conflict between codes, regulations, or standards, the most stringent requirement shall take precedence.

## 1.05 SUBMITTALS

- A. Product Data: Submit manufacturer's product data within four weeks of NTP for each system proposed for use. Include the following:
  - 1. Electrical characteristics and connection requirements.
  - 2. Expected heat dissipation of elevator equipment machine space and controller space BTU based on maximum possible full load starts per hour.

*Note to specifier: Machine space will likely mean that the hoistway, or a portion of the hoistway where the machine is located will need temperature control.*

- 3. Maintenance programs: within sixty (60) days after notice to proceed, and prior to installation, Contractor shall submit detailed interim and revenue service maintenance programs, showing functions to be performed and their scheduled frequency.

4. Coordinated delivery schedule
5. Manufacturers recommended preventive maintenance plan, including interim maintenance procedures where applicable.
6. Pre-acceptance test forms.

*Note to Specifier: Special loading requirements above shall be in accordance with the special duty table 1 at the beginning of this guideline.*

- B. Shop Drawings: Submit approval layout drawings to scale. Include the following:
1. Car, guide rails, buffers and other components in hoistway.
  2. Maximum rail bracket spacing.
  3. Maximum loads imposed on guide rails requiring load transfer to building structure. Include machine reactions and layout information.
  4. Loads on hoisting beams.
  5. Clearances and travel of car runby
  6. Clear inside hoistway and pit dimensions.
  7. Location and sizes of access doors, hoistway entrances and frames.
  8. Car and Hall fixtures.
  9. Machine loads, motor loads, calculations showing over design and factors of safety.
  10. Refuge space on top of car and pit.
  11. Hoistway layout.
  12. Controller and drive space layout

*Note to specifier: discuss AHJ issues that may arise for controller space locations.*

13. Signal and operating fixtures, operating panels and indicators.
14. Cab design, dimensions and layout.
15. Hoistway-door and frame details.

Note to specifier: (Optional specification for fast track projects:)

A. Shop drawings: Six (6) copies of the shop drawings (or cut sheets with standard dimensions if available) shall be provided by the Contractor for approval within three weeks of notice to proceed. All bearing ratings, identification and catalog numbers shall be provided.

## 1.06 OPERATING AND MAINTENANCE MANUALS

A. Operating and Maintenance manuals: Prior to installation, installer shall submit three (3) preliminary sets of Operation and Maintenance manuals for approval six weeks after Notice To Proceed: After Owner approval and prior to the beginning of acceptance testing, one (1) set of the approved manuals shall be provided by the installer as well as one copy on a DVD in a format approved by the Owner. After approval and substantial completion, the final manuals are due no more than 30 days after any punch list items are completed. The manuals shall include the following:

1. Complete table of contents.
2. Complete instructions regarding operation and maintenance of equipment. Included will be complete illustrated, exploded views of all assemblies, and a complete, illustrated, exploded view for identifying all system parts.
3. Complete nomenclature, lead time and location of replaceable parts, OEM and installer part numbers, current cost, and source. If product source is another vendor, Contractor shall include name and address of other vendor.
4. Copies of approved preventive maintenance plan.
5. Descriptions of safety devices.
6. Safety rules, tests, and procedures, including testing of all systems and subsystems.
7. Troubleshooting techniques.
8. Detailed lubrication and cleaning schedule indicating weekly, monthly, quarterly, semiannual, and annual lubrication; and a description of each lubrication point, lubrication type, and specification.
9. As-built drawings shall include:
  - a) Control and schematic electrical wiring diagrams of controller, including wiring of safety devices to connections with remote indication and control panels for each elevator and group of elevators.
  - b) Electrical layout showing placement of lighting, light switches, receptacles, light fixtures, disconnect switches, and convenience outlets in machinery and controller spaces and pits.
  - c) Complete detailed drawings and wiring diagram of elevator fault finding device and connection to annunciator panel.
  - d) Electronic and hard copies of ladder diagrams, logic and program.

### B. Certification:

1. The OEM shall provide to the owner certification, which the owner of the elevator(s) shall be provided with copies of all documents related to maintenance, safety, operations, design changes, modifications, retrofits, etc., Which relate to any part, component, equipment, system, subsystem, or material and services applicable to the elevator provided.
2. All of the above referenced shall be provided by the installer as it pertains



to the original installation through the end of the warranty period.

3. The referenced material shall be provided within thirty (30) days of publication or internal distribution by the OEM. The material, even if labeled PROPRIETARY, shall be delivered to the Owner without prejudice or delay and at no additional cost.

- C. Electronic material: Provide all material on CD-ROM in a format approved by the Owner.
- D. Material Safety Data Sheets (MSDS) and product data sheets: Shall be submitted with an index listing each product, along with the application method of the product, approximate quantity of product per elevator, and the component the product is applied to or associated with. The Contractor shall allow 6 (six) weeks for review of MSDS by the Owner.

### **1.07 TRAINING**

*Note to specifier: Properties with a 3<sup>rd</sup> party maintenance Contractor should not require as much time and training by the Contractor and can be reduced to 8 hours .Since MRL elevators are relatively new, the Owner may want to consider more training or site visits during construction to familiarize themselves with the new equipment. The specifier should clarify how many people need to be trained and how many material handouts are required. Timing of the training for Owner maintained facilities should be considered if the Installer is providing a period of Interim maintenance.*

- A. The Installer will provide 40 hours of local training for the Owner and his representatives in the proper use, operations, and daily maintenance of elevators. Review emergency provisions, including emergency access and procedures to be followed at the time of failure in operation and other building emergencies. Train Owner personnel in normal procedures to be followed in checking for sources of operational failures or malfunctions. Provide manuals for all material covered in the training program. This training will take place at the discretion of the Owner at any time prior to the end of the warranty period.
- B. (OPTIONAL) Provide a 60 minute (minimum) CD video or DVD describing and demonstrating daily maintenance, emergency procedures and troubleshoot techniques for electrical and mechanical failures and malfunctions.

### **1.08 QUALITY ASSURANCE**

Note to specifier: it is the recommendation of this working group to tighten this part of the specification as much as job circumstances and local procurement regulations permit.

- A. Manufacturer: Provide elevators manufactured by a firm with a minimum of 10 years experience in fabrication of elevators.
- B. Installer: Lead mechanics with a minimum of 10 years experience in installation of elevators. Documentation shall be required to document this requirement.
- C. Regulatory Requirements: Elevator system design and installation shall comply with

- the version of ASME A17.1 in effect for this contract.
- D. Permits and Inspections: Contractor to provide licenses and permits and perform required inspections and tests.

*Note to specifier: The following section may be appropriate in order to inspect and observe construction methods that would be difficult or impossible to observe after installation is complete.*

- E. Regulatory agencies: elevator design, materials, construction clearances, workmanship, and tests shall conform to the requirements of the codes and regulations listed in part 1.04, APPLICABLE CODES, STANDARDS, AND PUBLICATIONS.
- F. Welding: Welding shall be performed in accordance with the requirements of AWS or CWB. Welders shall produce evidence of current certification by AWS or CWB.
- G. Labeling: Every elevator controller shall be clearly marked permanently on the controller with rated load and speed, manufacturer serial number, and the designated Owner identification.
- H. Requirements of Regulatory Agencies
1. Contractor shall obtain and pay for all necessary permits, and perform such tests as may be required for acceptance and approval of elevators by jurisdictional agencies.
  2. Contractor shall notify the proper inspectors to witness required testing.
- I. (Optional) Factory Visit

*Note to specifier: Not all of the elevator components may be manufactured in the same location by the same manufacturer.*

1. The Contractor shall provide for the costs of up to three of the owner's representatives to visit the factory where the elevator is being manufactured.
2. The Contractor shall not ship the elevator without the approval of the owner after the conclusion of the factory visit.

## **1.09 DELIVERY, STORAGE AND HANDLING**

Should the building or the site not be prepared to receive the elevator equipment at the agreed upon date, the Contractor will be responsible to provide a proper and suitable

storage area on or off the worksite.

## **1.10 WARRANTY**

A. The acceptance is conditional on the understanding that their warranty covers defective material and workmanship. The warranty period shall be one (1) year from the date of Beneficial Use. The warranty excludes ordinary wear and tear or improper use, vandalism, abuse, misuse, or neglect or any other causes beyond the control of the elevator Contractor and this express warranty is in lieu of all other warranties, express or implied, including any warranty of merchantability or fitness for a particular purpose.

*Note to specifier: section 1.10.B is an option for third party maintenance during the warranty period*

B. Interim maintenance is required between Beneficial Use and Revenue Service. This service will be performed according to the approved maintenance plan, with no extra charge for overtime required to return the elevator to service. Vandalism and acts beyond normal wear and tear are excluded.

C. Deliverables: Proof of interim maintenance: documents will be required prior to Final Acceptance.

## **1.11 MAINTENANCE SERVICE**

*Note to specifier: The contract document should provide minimum response times for regular time, over time and entrapments.*

A. The approved maintenance service consisting of regular examinations, adjustments and lubrication of the elevator equipment shall be provided by the elevator Contractor for a period of 12 months after the elevator has been turned over for the Beneficial Use. This service shall not be subcontracted but shall be performed by the installer. All work shall be performed by competent employees during regular working hours of regular working days and shall include 24-hour callback service at no extra cost. This service shall not cover adjustments, repairs or replacement of parts due to negligence, misuse, abuse or accidents caused by persons other than the elevator Contractor. Only parts and supplies as used in the manufacture and installation of the original equipment shall be provided.

B. Deliverables: Proof of maintenance, documents and all as built documents to complete the O&M manuals will be required prior to Final Acceptance.

## **1.12 DESIGN CRITERIA:**

A. General

Elevators shall be designed with provisions for thermal expansion and contraction of complete elevator assemblies.

B. Operational Requirements

1. Hours of operation shall be considered as twenty-four (24) hours per day, seven (7) days per week.
2. Elevator components shall be designed based on the following applied duty cycle during operation:

Three (3) Hours with 100% Rated Load

Six (6) Hours with 50% Rated Load

Fifteen (15) Hours with 25% Rated Load

*Note to specifier: The above noted duty cycle is a general reference to stipulate anticipated load cycles encountered during normal operation. Duty cycles are utilized in design calculations for components to determine compliance with design and life requirements. Anticipated load, or duty, cycles should be reviewed and amended as needed for the anticipated usage requirements.*

3. Maximum dwell time per landing in these calculations shall be no more than 10 seconds.

C. Environmental Requirements

*Note to specifier: Interior installations include facilities such as airports and controlled environments with no corrosive elements. Exterior installations should be used for all light rail, heavy rail, commuter rail and bus applications whether exposed to the weather or not.*

1. General: Elevators shall be capable of operating with full-specified performance capability while exposed to the following climatic and environmental conditions.
  - a. Interior installations: Elevators shall be designed to operate in a temperature range of plus five (+5) to plus one hundred and twenty (+120) degrees Fahrenheit, dry bulb; and all conditions of relative humidity while exposed to airborne dust and debris.
  - b. Exterior installations: Elevators shall be designed to operate while exposed to the natural elements of weather, including sunlight, rain, slush, snow and ice; all conditions of relative humidity while exposed to salt, de-icing chemicals, airborne dust, and debris, and corrosive elements; and in a drybulb temperature range of minus twenty five ( -25) to plus one hundred and twenty (+120) degrees Fahrenheit.

D. Bearings

1. Bearings: All fixed machine and motor bearing housings shall be provided with a drilled, tapped and spot faced area in the vertical and axial axis to accommodate a transducer that a Fast Fourier Transform (FFT) analyzer requires. Permanently mount transducers on the drive bearings or where recommended by the machine manufacturer and run the wires into the controller to a panel with BNC connectors on the ends to accommodate the FFT analyzer.
  - a. Motor limit: rigid mount: .15 ips flex mount: .2 ips
2. Bearings shall be rated for an AFBMA L10 life as specified, under fluctuating bearing load. All bearings shall have basic dynamic load ratings.

E. Fasteners

1. Fasteners shall be compatible with materials being fastened.
2. Fasteners shall be furnished with self locking nuts or retaining rings (spring washers, toothed disks).
3. Fasteners shall be equal to or of greater corrosion resistance than the most corrosion resistant metals being fastened.

F. Ride Quality

1. All elevators shall have a maximum decibel reading of 70 Dba with the doors closed during a run in the up direction, measured 5 feet above the floor in the center of the cab.

*Note to specifier: Ride quality information can be found in great detail in the National Elevator Industry Inc. Design guideline manual. APTA considered adopting a milli-g requirement of 35 milli-g in each axis in a raw format. A95 is an average of the peak to peak readings of the raw data to weed out inequities in collecting data or in frequencies outside human perception. However, the Working Group considers vibration requirements too stringent for most transit environments. Special consideration should be given to the application before requiring a vibration ride quality requirement. A better alternative may be to establish a benchmark at acceptance that should be maintained during the life of a maintenance agreement.*

*When measuring Dba, be certain to take station ambient noise levels when testing.*

**1.13 JOB CONDITIONS:**

- A. Protection: During installations, and until elevator systems are fully operative, Contractor shall make necessary provisions to protect systems from damage, deterioration, injury to pedestrians, the general public and environmental conditions.
- B. Coordination Requirements

1. Alterations: Contractor shall coordinate any alterations required to accommodate elevators with the Owner.
2. Floor finish in cab: Contractor shall install cab flooring as specified.
3. Lock and key requirements: Contractor shall coordinate with the Owner.
4. Pit Drainage: Contractor shall coordinate location of sump pits, pumps, pipes and related wiring with elevator installer.

Note to specifier: Elevator code prohibits connections of elevator pit drains to sanitary lines.

5. Installation Plan: Contractor shall supply an installation plan that is approved by the Owner.
6. Safety Training: Contractor shall attend appropriate safety training programs provided by the Owner at no extra cost.
7. Methodology: The Contractor shall meet with the Owner and provide a written method of installation for approval.
8. Electrical: The installer shall coordinate with the Contractor and appropriate trade in relation to CCTV, communications, smoke detectors, shunt trip breakers, power and cab lighting requirements.
9. Construction schedule: Installer shall coordinate deliveries, installation and testing with the Contractor.

## PART 2 PRODUCTS

Note to specifier: This portion of the guidelines will encompass both geared and gearless MRL applications.

### 2.0 ACCEPTABLE MANUFACTURER

**Provide MRL elevators as specified.**

#### 2.01 SUMMARY OF FEATURES

##### A. Elevator Number:

- |                              |                       |
|------------------------------|-----------------------|
| 1. Elevator Use:             | Passenger             |
| 2. Contract Load, in pounds: | per contract drawings |
| 3. Contract Speed, in FPM:   | as specified          |

*Note to specifier: the minimum elevator speed should not be lower than that required to run the elevator the full length of travel in no more than 30 seconds.*

- |                     |                       |
|---------------------|-----------------------|
| 4. Travel Distance: | per contract drawings |
| 5. Serves:          | per contract drawings |
| 6. Number of Stops: | per contract drawings |

- |  |   |
|--|---|
| <b>7. Number of Openings:</b>  | <b>per contract drawings</b>  |
| <b>8. Machine Location:</b>  | <b>per contract drawings</b>  |
| <b>9. Machine Type:</b>  | <b>As specified</b>   |
| <b>10. Car and Hoistway Door Size:</b>   | <b>per contract drawings</b>  |
| <b>11. Car and Hoistway Door Type:</b>   | <b>per contract drawings</b>  |
| <b>12. Car and Hoistway Door Operation:</b>  | <b>Power High-speed, heavy duty<br/>(Minimum opening speed 3.0 FPS)</b> |
| <b>13. Hoistway Entrance:</b>  | <b>New, as specified.</b>   |
| <b>14. Cab Enclosure:</b>  | <b>New, as specified.</b>   |
| <b>15. Door-Reversal Device:</b>   | <b>Non Contact door reversal device</b>                                 |
| <b>16. Car Operating Panel:<br/>resistant features</b>   | <b>Stainless Steel with vandal</b>                                      |
| <b>17. Car Position Indicator features</b>   | <b>Stainless Steel with vandal resistant</b>                            |
| <b>18. Car Direction Indicator features</b>  | <b>Stainless Steel with vandal resistant</b>                            |
| <b>19. Hall Call Stations:<br/>resistant</b>   | <b>Single riser, stainless steel with vandal buttons</b>                |
| <b>20. Communication System:</b>   | <b>“Hands-Free”</b>   |
| <b>21. Provide keyed switch in car operating panel or hall pushbutton station as directed to shut down elevator.</b> |   |

## **2.1 MACHINE COMPONENTS**

### **A. MOTOR:**

1. Bearings shall be rated with an AFBMA L10 life of 65,000 hours.
2. The motors shall be of the alternating current reversible asynchronous or synchronous type of a design adapted to the severe requirements of elevator service. Motor shall be capable of developing the torque required to meet or exceed an acceleration rate of 2 ft/sec<sup>2</sup> for the elevator car.

3. A means to protect the windings and bearings from airborne dust shall be provided.
  4. Insulation of all windings shall be impregnated and baked to prevent absorption of moisture and oil. The insulation resistance between motor frame and windings shall not be less than one megohm. The motor windings shall stand a dielectric test of twice the normal voltage plus 1000 RMS volts of 60 Hertz, alternating current for one minute.
  5. Motor leads in the conduit box shall have the same insulation class as the windings. Motor lead wire shall be rated 125 C and shall be sized for 105 C at the motor nameplate amperes at 1.0 Power Factor per Electrical Apparatus Service Association (EASA) recommendations. Leads are to be numbered for clockwise rotation when facing opposite the shaft end.
  6. The motor shall be designed to stand the severe loads encountered in elevator service and the windings shall have a minimum insulation temperature rating two ratings higher than the actual temperature rise of the motor, with a minimum rating of NEMA class F.
  7. The motor shall be designed to the ASME A17.1 rated load requirements.
- C. BRAKE: The brake(s) shall be of the self adjusting fail-safe (spring applied and electrically released) type provided with an external manual brake release and designed to meet the service factor demand of its intended use.

#### F. Geared MRL Machines

1. GENERAL CONSTRUCTION: The hoisting motor shall drive a grooved sheave through an approved means of transmission.
2. MOTOR: The hoisting motor shall be reversible alternating current, operated through Variable Voltage Variable Frequency drive. Motor speed shall not exceed 1800 RPM.
3. BRAKE: Disc or drum brake shall be securely mounted to the shaft and shall run concentric to the shaft. Disc or drum shall be machined to obtain a smooth and accurate face. The brake shall be spring actuated, direct current, electrically released, heavy construction with proper braking area for the load and speed specified. The brake shall be provided with sufficient power to stop and hold the car with full contract load. Drum brakes shall have two (2) shoes actuated by two separate compression springs. Disc brakes shall be of caliper or multiple disc design
4. SHEAVE: The sheave material shall be accurately machined of semi-steel of hardness BHN 220-250.
5. GEAR HOUSING: The gear housing shall be divided horizontally at the centerline of the shaft to provide access to the gear. Suitable drain plugs and overflow pipes shall be provided.
6. MOUNTING: The gear housing, brake support and motor support (if foot-mounted



motor) shall be mounted on a rigid bedplate.

7. ALIGNMENT OF HIGH SPEED SHAFTS: Motor, brake and gearing shall be accurately aligned in the factory for total indicator readout not exceeding .007" TIR. Flange-mounted motors shall be aligned with the gear housing through machined registers. Foot-mounted motor alignment must be checked again after installation in the building, and when full load is applied; if alignment is not with the .007" TIR specified, then the motor, brake pulley and worm shaft are to be re-trammed on site.
8. ALIGNMENT OF WORM AND GEAR: There should be no hard contact with worm on either corner or edge of gear tooth. Machines with adjustable sheave shafts shall have worm and gear this alignment field checked per the manufacturer's recommendation after the machine is set and load applied.
9. DYNAMIC BALANCE: The worm and its shaft, and the sheave, gear and gear spider shall be dynamically balanced as required to eliminate any source of noise or harshness.

G. Gearless Machine:

1. SHEAVE: The sheave material shall be accurately machined of semi-steel of hardness BHN 220-250.

**2.11 CONTROLLER**

*Note to specifier: remote monitoring is an important part of elevator installations in public transportation facilities. This document will provide elevators capable of connections to many transit SCADA systems. This document does not provide any design guidelines for remote monitoring beyond providing PLC controls for the elevators.*

- A. A PLC-based controller shall be provided, governing starting and stopping, as well as preventing, damage to the motor from overload or excessive current. It shall automatically cut off the motor current and bring the car to rest in the event any of the safety devices are activated. The controller shall be mounted in a vented cabinet within the controller space room. The controller shall utilize soft start characteristics.

(Optional) The controller shall be designed to operate automatically on standby power.

1. Selective Collective Operation: As defined by ASME A17.1.

- B. Provide a separate battery powered unit that senses loss of power. Battery shall be 12 volt minimum, sealed nickel cadmium or gel cell construction. When loss of power occurs, elevator shall ascend or descend to nearest landing and open doors automatically. After a predetermined time, the doors shall close and the elevator shall remain inoperative until normal power is restored. The door open and alarm buttons shall operate under battery power. Reduced speed for evacuation on battery operation is permitted.

C Elevator Drive System:

*Note to specifier: Most standard VVVF drives are non-regenerative, which means that the overhauling loads will generate heat in a resistor bank, usually located near the drive system. Fully regenerative drives are possible with the addition of a second VVVF drive and special engineering. This will add cost to the installation, but will reduce the BTU output by the drive and have implications for standby power as well.*

1. Non-Regenerative Variable Voltage Variable Frequency Drive. The drive shall be microprocessor and IGBT based using vector control algorithms. The algorithms shall incorporate a motor model to determine the electromagnetic state of the motor. The motor model shall also encompass a temperature compensation algorithm which is essential for speed accuracy.
2. Velocity shall be controlled by a feedback loop to within +/- 2% of contract speed and speed shall be independantly supervised.
3. Position of floors in the building shall be learned during a slow speed setup run. Once learned, floor locations shall be stored in non-volatile memory. Power loss shall not require the floors to be re-learned. Stopping accuracy shall be +/- 5 mm or less. Re-leveling shall be automatic.
4. Resistors shall be provided to absorb the power regenerated by the motor. They shall dissipate power only when the motor is regenerating. Control shall be by IGBT.

D. Maximum total harmonic distortion shall not exceed IEEE Std. 519 to be measured at the elevator disconnect.

*Note to specifier: There are two main types of VVVF drives now available; regenerative and non regenerative. While the regenerative is more expensive, the BTU output is almost half that of a non-regenerative system which absorbs the regenerative energy into a resistor bank.*

2.12 SAFETY DEVICES: Shall be provided in accordance with the edition in effect of ASME A17.1 and any local jurisdictional requirements.

2.13 HOISTWAY

- A Roller Guides: Roller guides shall be mounted on top and bottom of the car frames to engage the guide rails.
- C. Car Guide Rails: Tee-section steel rails with brackets and fasteners.
- D. Buffer: per code.
- E. Means of suspension: per code. If steel core ropes are supplied, a means to provide constant lubrication shall be provided. An alarm indicator shall be provided when the oil reservoir is at 25% of capacity.

Other types of suspensions means are becoming available and may require additional

maintenance or design considerations. Coordination with the supplier is essential when the job is designed.

### 2.3 WIRING:

*Note to specifier: All wiring should be rated one size over the NEC table requirements for conductors. All interior elevator locations should use NFPA ratings for damp conditions, while outdoor locations should be rated for wet locations. Interior installations with a high water table should be rated for wet locations.*

#### 1. Conduit and Wiring

##### A. Cables and Conductors

- a. Unless otherwise specified, all electrical conductors in the pits and hoistways, except traveling cable connections to the car shall be provided in rigid steel conduit with steel outlet boxes, except that a small amount of flexible conduit may be used where conduit is not subject to moisture or embedded in concrete
- b. Rigid steel conduit shall be full weight, threaded, hot-dip galvanized, inside enameled, conforming to ANSI C80.1.
- c. Conduit fittings and bodies shall meet ANSI/NEMA FB 1; threaded type, material to match conduit.
- d. Terminal boxes, pull boxes and other similar items, shall be of approved construction, thoroughly reinforced, and shall meet ANSI/NEMA FB 1.
- e. All electrical boxes exceeding 150 cubic inches shall be supported independently of the conduits.
- f. All raceways shall be threaded rigid steel conduit complying with ANSI/NEMA FB 1.
- g. Where permitted flexible heavy-duty service cord, type SO, may be used between fixed car wiring and switches on car doors for safety edges and light ray devices for reversal devices.
- h. Where permitted, flexible metal conduit shall be fabricated in continuous length from galvanized steel strip, spirally wound and formed to provide an interlocking design with a gray XLPO Thermoset Type 2 outerjacket.
- i. All conduit terminating in steel cabinets, junction boxes, wireways, switch boxes, outlet boxes and similar locations shall have approved insulation bushings. If the bushings are constructed completely of insulation material, a

steel locknut shall be installed under the bushing. At ends of conduits not terminating in steel cabinets or boxes, the conductors shall be protected by terminal fittings having an insulated opening for the conductors.

- j. All conduits terminating in NEMA 4X boxes shall be backed up with flat rust resistant steel plates to fit the entire area where the conduit penetrated the box.
- k. All conduit fittings and connections shall be compression type. The use of set screw or indentations as a means of attachment is not permitted.
- l. Connect motors and other components subject to movement or vibration, to the conduit systems with flexible conduit.
- m. The Contractor shall furnish all materials and completely wire all parts of the electrical equipment of the elevators including electrical devices on hatch doors.
- n. All solid state and electrical components located on top of the car enclosure or in the hoistway shall be installed within NEMA 4X enclosures.
- o. Conduits shall be brought and connected to suitable approved connection boxes at all outlets, apparatus and panels.
- p. Conduit Sizing, Arrangement, And Support
  - 1. Size conduit per NEC for conductor type installed or for Type THW conductors, whichever is larger; 3/4-inch minimum size for conduit.
  - 2. Conduits for small devices such as door switches, interlocks, etc. shall be permitted at 1/2 inch
  - 3. The total overall cross sectional area of the wires contained in any conduit shall not exceed 40 percent of the internal area of the conduit.
  - 4. Arrange conduit to maintain headroom and present a neat appearance.
  - 5. Route exposed conduit parallel and perpendicular to walls and adjacent piping
  - 6. Maintain minimum 6-inch clearance between conduit and piping. Maintain 12-inch clearance between conduit and heat sources such as flues, steam pipes, and heating appliances.
  - 7. Arrange conduit supports to prevent distortion of alignment by wire pulling operations. Fasten conduit using galvanized straps, lay-in adjustable hangers, clevis hangers, or bolted split stamped galvanized hangers.
  - 8. Group conduit in parallel runs where practical and use conduit

- rack constructed of steel channel with conduit straps or clamps. Provide space for 25 percent additional conduit on racks.
9. Do not fasten conduit with wire or perforated pipe straps. Remove all wire used for temporary conduit support during construction, before conductors are pulled.
  10. No conduit shall be attached to a cable tray or installed within 6 inches of a cable tray or light fitting except for termination.
  11. Approved strain boxes shall be installed for all vertical runs in accordance with Code.
- q. Where conduit penetrates fire-rated walls and floors, seal opening around conduit with UL listed through penetration firestop system to maintain wall or floor rating.
  - r. All interlock, hall button and limit switch branch wiring shall be enclosed in flexible steel conduit with covering of liquid tight Type "EF" with connectors having nylon insulated throat.
  - s. All screws used for terminal connections of all wiring (machine room, hoistway and pit) shall be provided with "star washers" of proper size and type.
  - t. All existing conduit and wiring shall be removed and wall/floor slabs patched with fire rated material.

#### B. Conductors

- a. Unless otherwise specified, conductors, exclusive of traveling cables, shall be 98% conductivity copper, solid, for size 10 AWG and smaller, and stranded for size 8 AWG and larger shall be stranded or solid coated annealed copper in accordance with the NEC for Type THHW.
- b. Where 16 and 18 AWG are permitted by Code, either single conductor cable in accordance with Code for Type TF, or multiple conductor cable may be used provided the insulation of single conductor cable and outer jacket of multiple conductor cable is flame retardant and moisture resistant.
- c. Insulation Voltage Rating: 600 volts.
- d. Insulation: ANSI/NFPA 70, type THHN/THWN, XHHW or THW.
- e. The use of PVC insulation shall not be permitted.
- f. Color Coding: All power conductors identified as to phase and voltage by means of color impregnated insulation, as follows:

Voltage	ØA	ØB	ØC	Neutral	Ground
120/208V	Black	Red	Blue	White	Green
277/480V	Brown	Orange	Yellow	White	Green

For wire sizes No. 8 AWG and larger, color banding tape, minimum 2 inches wide, may be used at all accessible locations in lieu of colored insulation.

- g. Multiple conductor cable shall have color coding or other suitable identification for each conductor. Conductors for control boards shall be in accordance with Code.
- h. No joints or splices shall be permitted in wiring except at outlets. Tap connectors may be used in wireways provided they meet all UL requirements.
- i. All wiring shall test free from short circuits or grounds. Insulation resistance between individual external conductors and between conductors and ground shall be not less than one meg-ohm.
- j. Where size of conductors is not given, capacity shall be such that maximum current shall not exceed limits prescribed by Code.
- k. Equipment grounding shall be furnished and installed. Ground conduits, supports, controller enclosures, motors, platform and car frames, and all other non-current conducting metal enclosures for electrical equipment in accordance with Code. The ground wires shall be copper, green, insulated and sized as required.
- l. Terminal connections for all conductors used for external wiring between various items of elevator equipment shall be solderless pressure wire connectors in accordance with Code. The Contractor may at his option make these terminal connections on No. 10 or smaller conductors with approved terminal eyelets set on the conductor with a special setting tool, or with an approved pressure type terminal block. Terminal blocks using pierce-through serrated washers are not acceptable.
- m. Provide all necessary conduit and wiring between all remote machine room and hoistway.

### C. Traveling Cables

- a. Traveling cables from junction box on car to junction box in hoistway shall consist of flexible traveling cables conforming to the requirements of Code.
- b. Junction boxes in hoistway and on car shall be equipped with terminal blocks. All connections to terminal blocks shall be made with either terminal eyelet

connections or pressure wire connectors of the clamp type that meet UL 486 requirements for stranded wire.

- c. Terminal blocks shall have permanent indelible identifying numbers for each connection. The outer covering must remain intact between junction boxes. Abrupt bending or twisting producing distortion of cable is not permitted.
- d. Cables shall be free from any possible contact with hoistway structure, car or other equipment. Furnish and install shields or pads to protect the cables.
- e. Travel cables shall include, as a minimum:

NOTE TO SPECIFIER – COORDINATE TRAVELLING CABLE REQUIREMENTS WITH OWNERS SECURITY REQUIREMENTS IE CARD READERS, CAMERAS , ETC

- 1. 2 coaxial cables shielded for the CCTV system.
- 2. 4 cat 5 twisted shielded pairs for security and telephone systems

- f. Provide separate traveling cables for car lighting and fan control circuits.
- g. Provide traveling cable for telephone in the elevator car. Cable shall extend from junction box in hoistway to telephone box in car.
- h. Provide traveling cable for car work lights. Cable shall extend from junction box in hoistway to car junction box.
- i. Car and hoistway junction boxes shall be provided for on the top of the elevator cab.
- j. Cables shall include ten percent spare wires between each controller, selector, and hoistway junction box, all spares to be properly tagged or otherwise identified with clear and indelible markings.
- k. All insulated wiring, control wiring and wiring in traveling cables shall be tag coded at their terminals in the motor room, and hoistway junction box, elevator cab junction box, and push-button stations within the cab, and shall agree with the approved wiring diagrams.
- l. The traveling cable shall be wired directly from the controller to the elevator with no hoistway junction box.
- m. The emergency stop switch in the car shall be connected to all alarm bells in a manner that will cause the bells to ring when the emergency stop switch is in the "On" position.

- D. All cabinets containing motor drives, filter boxes, transformers and power reactors shall be supported on rails and isolated from the base building structure with elastomer pads having a minimum static deflection of 3/8" (Mason Type N, or

equivalent). All connections to and from the cabinetry shall be flexible in order not to compromise the isolation system. Use flexible conduit for the final electrical connection, with all other conduit supports and clamps provided on a neoprene sponge insert. Cabinets shall be NEMA 4X.

Note to specifier: Careful coordination with other engineering disciplines is required to assure proper grounding methods are followed in the elevator machine room as well as proper steps to reduce noise on VFAC elevator drive systems.

- E. Supply, installation and connections of fused main line disconnect switch of the lockable type for the elevator.
- F. Signal to the controller to indicate special emergency condition due to lobby smoke detector activation; and smoke detectors in the elevator lobby and controller space in accordance with the ASME A17.1 code.
- G. Car lighting and fan circuit for the elevators shall be located in circuit breaker panel in the controller space.

### **2.3 CAB ENCLOSURE**

*Note to specifier: Cab finishes are typically designed by an architect. This section provides the cab shell, cab front, floor and dome only. The final cab finishes should be detailed in the bid drawings developed in coordination between the architect and the elevator designer. This guideline is focused on key items for materials and finishes.*

*Plan on stainless steel type 316 #4 or hairline finish with vertical grain as a minimum for all stainless steel.*

*Poured epoxy floors are recommended rather than tile or diamond plate flooring.*

*Although an elevator car sized to fit a gurney or emergency stretcher is not required by A17.1, it may be a requirement of the Local Governing Code and is recommended for consideration.*

*Where fire-rated shaft construction is required for an elevator hoist way, the Car enclosure shall be solid on all sides.*

*Where solid shaft construction is not required, the hoist way and the Car enclosures may be partially glass. An observation Car may have glass on a minimum of one wall or a maximum of three walls including glass entry Car doors or doors with vision panels.*

*The glass observation panels should be operable, opening into the car so that the panels can be cleaned and access is provided for cleaning the hoist way glass panels from within the car. A17.1 Code requirements include the following, which must be reviewed by the designer:*

*A stationary panel must be 3'-6" in height below the panel that opens, the*



*open panel must have locks and safety shutoff feature as required by Code and a handrail must be at each glass observation panel. The designer must coordinate with the car manufacturer and establish that the operating panel size of 9/16" glass does not exceed the limitations of the hinges used.*

## 2.4 CAB ENCLOSURE

A. Cab configuration and materials shall be per contract drawings prepared by the architect and as specified herein.

B. Cab Flooring:

1. Appropriate floor materials include:
  - a. Chemical Resistant Urethane
  - b. Terrazzo with Marble Chips in Epoxy
  - c. Clear Epoxy Resin with Vinyl Chips
2. Seamless and resilient elevator cab flooring shall be poured or laid in accordance with manufacturer's instructions over a type 316 stainless steel platform.
3. Resilient flooring systems shall be self-extinguishing, have 200° F. heat resistance, 11,700 PSI compressive strength, 2,200 PSI tensile strength, and 5,000 PSI flexural strength.

## 2.5 CEILING TYPE

A The clear height under the ceiling canopy shall be a minimum of 8'-0". Ceiling canopies shall be stainless or enameled steel not less than 0.109" nominal thickness.

*Note to the Specifier: It cove lighting is used at non-entry walls the underside and return of the cove shall be 12-gauge type 316 stainless steel, #4 brushed finish with grain running the direction of the cove. Each corner of the cove shall be reinforced with hangers same gauge as the cove. A vandal resistant lens cover shall be placed between the cove return and ceiling.*

B. Ventilation: 2-speed exhaust fan. Finish and material of fan enclosure and blade shall match the finish and material of the ceiling having a NEMA

4X rating. Exhaust blowers shall be designed with a hood.

*Note to Specifier: The material selection, type, pattern and finish requires careful consideration for durability, ease of maintenance and appearance for Finished Solid Enclosures.*

*Materials and finishes for exposed parts of elevator car enclosures shall include:*

*Satin Stainless Steel: ASTM A 666, Type 316, with Hairline Vertical satin finish.*

*Textured Stainless Steel: ASTM A 666, Type 316; titanium nitride or oxide colored; with coined or embossed texture rolled into exposed surface. Surface may be satin polished, satin relieved, color coated and satin relieved or color coated and bright relieved after rolling.*

*Note to specifier: Textured stainless steel products may be used particularly where there is no or little exposure to deicing or coastal salt. Crevice corrosion can be a significant problem in coastal areas. It is advisable to use textured stainless steel above wainscoting, not below where moisture and salts will cause corrosion.*

*Nickel Silver Extrusions: ASTM B 151 (ASTM B 151M), alloy UNS No. C74500.*

*The desired thickness of stainless steel should always be shown in inches. ASTM does not define stainless steel gauges and each producer has their own definition. The specifier will have no legal protection if a gauge number is specified and the thickness is not what was desired. List a minimal thickness or a nominal thickness with an acceptable tolerance variation. The nominal thickness typically associated with 12 and 14 gauges are as follows:*

*12 gauge - 0.109 inches (nominal)*

*14 gauge - 0.078 inches (nominal)*

*Most stainless steel finishes with an obvious grain are directional. If all the panels are not installed in the same rolling or polishing direction, there will be color variation from panel to panel.*

#### *Observation Cars*

*Where glazing is used, safety-glazing material must be specified in accordance with ANSI Z97.1. These are defined as glazing constructed, treated or combined with other materials to minimize cutting and piercing injuries when broken by human contact. The following when in compliance with ASME A17.1 and Z97.1 may be used:*

*Laminated Glass: Two or more sheets of glass held together by an interlayer(s) of plastic material.*

*Tempered Glass: A single sheet of specially heat or chemically treated glass which cannot be cut, drilled, milled or polished after treatment.*

*Wired Glass: A single sheet of glass with wire completely embedded in it.*

*Safety Plastic: A single or multiple sheets laminated of synthetic plastic in the form of fibers or flakes which are poured and molded and which contain an organic substance of large molecular weight.*

*Organic Coated Glass: A single sheet of glass with an applied organic coating (plastic) on one or both sides.*

*Safety Insulating: Two or more sheets of glazing separated by air space as a complete assembly.*

*Where enclosures include panels of glass, transparent or translucent plastic, they shall be a minimum 9/16" thick laminated glass complying with 16 CFR Part 1201.1, 1201.2; laminated or safety glass or plastic complying with CAN/CGSB-12.1.*

## **2.6 HANDRAIL TYPE**

- A. Handrails: 1-½ inches outside diameter type 316 stainless steel #4 brushed finish and wall connectors shall have security type fastenings and shall be the same material and finish as the handrail. Handrail height shall conform with Code requirements placed on non-entry walls.
- B. The handrail shall be able to support a load of 600 pounds measured in the center of the rail without separating from the wall.

## **2.7 HOISTWAY EQUIPMENT**

- A. Entrance frames shall be of welded or bolted construction for complete one-piece unit assembly. All frames shall be securely fastened to fixing angles mounted in the hoistway and shall be of 2 mm type 316 stainless steel. Provide an additional type 316 stainless steel sill angle support. The sill shall be type 316 stainless steel.
- B. Doors: Entrance doors shall be of hollow metal construction with vertical internal channel reinforcements. Panels front and rear, framing, operating levers, and integral hardware shall be type 316 stainless steel; panel shall be 2mm and have a No. 4 finish.
- C. Entrance Finish: Finish shall be type 316 stainless steel #4 finish.
- D. Sight Guards: type 316 stainless steel

Note to specifier: hoistway fascia can be avoided by recessing the hoistway landing sills, or if ASME A17.1 2000 rules apply by providing a door lock on the

car door. It is recommended to plan on fascia in all front and rear opening installations.

- E. Fascia: shall be type 316 stainless steel.
- F. Provide sill mounted closers at all landings.
- G. Provide a vandal resistant access key switch in top and bottom landings.

## 2.7 Car Frame

A suitable car frame shall be provided with adequate bracing to support the platform and car enclosure. Provide welded or bolted ASTM 123 galvanized or type 316 stainless steel channel uprights affixed to crosshead and plank channels with welded or bolted bracing members and gusset plates which will remove strain from car enclosure.

## 2.8 Platform, Heavy Loading Type

The car platform shall be designed to accommodate one-piece loads weighing up to 25% of the APTA rated load, such as wheeled food carts, hand trucks, etc. The platform shall be type 316 stainless steel.

## 2.9 Equipment: Signal Devices And Fixtures

*Note to specifier: ASME A17.1 has specific requirements for key schedules, fire service keys, access keys and machine room keys. This should be reviewed during the development of the final specifications. Consideration should be given to high security locks in areas accessible to the public.*

- A. Car-Operating Panel: A type 316 stainless steel #4 vertical finish panel shall be provided with vandal resistant push buttons designed to bottom out against the panel plate and not the contacts, key switches.
- B. Provide one car swing operating panel integral with a stationary return panel.
- C. Braille/Arabic designations shall be flush with inconspicuous mechanical mounting.

Note to specifier, larger buttons for car and hall stations may be worth considering for improved visibility for the disabled community. Vandal resistant buttons are still required.

- D. Provide a service cabinet with a locked flush hinged or sliding door and integral certificate frame. Certificate Frame shall have durable Plexiglas window and be accessible from backside of

locked door. Minimum window size, to be approved by the Owner. Cabinet shall contain the following key type controls:

1. A light switch.
2. Two speed fan switch.
3. Inspection switch, conforming with the Code.
4. Independent service switch.
5. A duplex 120 volt, A.C. GFI convenience outlet.
6. Emergency Stop switch.

E. Engrave the car operating panels with the following:

1. No Smoking. Minimum 1" high lettering and graphic symbol
2. Elevator Number over operating buttons. Minimum 1/4" high lettering.
3. Elevator Capacity. Minimum 1/4" high lettering.
4. Firefighters Operating Instructions. Minimum 1/8 inch high lettering.

F. Car Position Indicator: A vandal resistant car position indicator shall be provided integral with the car operating panel.

*Note to specifier: ADA requires 2 way communications between the cab and the outside world. ASME A17.1 also requires communication between remote machine rooms and the elevator cab. This can mean at times that there are two modes of communication in the elevator cab.*

G. Communication: A hands free communication device shall be provided which has been designed in response to ADAAG requirements.

H. Car Lantern and Chime: A stainless steel vandal resistant directional lantern visible from the corridor shall be provided in the car entrance. When the car stops and the doors are opening, the lantern shall indicate the direction in which the car is to travel and an adjustable electronic chime will sound.

I. Hall Fixtures: Hall fixtures shall be provided with necessary stainless steel vandal resistant push buttons and key switches for elevator operation. Raised markings shall be provided for each push-button

J. Landing Passing Signal: An adjustable electronic chime bell shall sound in the car to tell a passenger that the car is either stopping at or passing a floor served by the elevator.

## 2.10 Door Operator Equipment

- A. Provide a GAL MOVFR-HSL or approved equal door operator with VVVF drive and the following features:
1. ½ hp motor and heavy duty sprocket, chain, belt, and sheaves.
  2. Closed loop regulated speed performance.
  3. Hand-held keypad programming.
  4. Adjustments can be stored in the keypad and downloaded to another operator.
  5. Adjustable door obstruction reversal.
  6. Optical cams with LED indicators.
  7. Test switches for open, close, nudging and speed zone set up.
  8. Universal inputs for open, close, and nudging.
  9. Reversing switch to back up the door reversal device.
- B. Provide a non contact door reversal device with light immunity: The Door Reopening Device shall cause both the car and hoistway doors to reverse, should they detect an obstruction in the elevator entrance. The device electrical wiring shall be supplied with quick disconnects terminals to facilitate replacement. The infrared curtain detector shall include the following:
- i. A protective infrared detector field extending from 1 1/2" above the car sill to a height of 68".
  - ii. A fail-safe control system to prevent the doors from closing in case of power loss to the detector.
  - iii. A one-piece full door height protective lens cover designed to be completely waterproof and to withstand impact, abrasion and vandalism.

## Part 3.0 EXECUTION

*Note to specifier: Be sure to include any Dba or vibration testing if included in the design criteria in part one of this guidelines.*

- 3.01. Contractor shall install complete and operating elevators in accordance with OEM's instruction and approved shop drawings.

*Note to specifier: clear instructions must be spelled out in the general terms and conditions relating to the installer being ready for the inspection, as well as the Owner being ready for items such as emergency power testing, fire alarm and smoke detector testing and communications. Special consideration should be given to AHJ lead times to schedule acceptance tests.*

## 3.02 FIELD TESTING:

A. General

1. Contractor shall notify the Owner seven (7) days prior to each scheduled test Contractor shall perform testing in the presence of an Owner representative.
2. Contractor shall notify the appropriate local authorities having jurisdiction a minimum of seven (7) days in advance of final acceptance tests.
3. Contractor shall provide all instruments, materials, and labor required for tests specified herein.
4. Contractor shall pre-test all devices within his control and provide documentation to prove compliance prior to jurisdictional inspection.

B. Acceptance testing requirements

1. Testing shall be performed in accordance with ASME A17.2.1 procedures with the following additions or adaptations.

C. Test Period: The elevator shall be subjected to a test for a constant period of 24 hours continuous run, with full specified A17.1 (not APTA) load in the car. During the test run, the car shall be stopped at all floors in both directions of travel for a standing period of 10 seconds per floor without tripping the motor overload device.

D. Speed Load Tests: The actual speed of the elevator car shall be determined in both directions of travel with full contract load and with no load in the elevator car. Speed shall be determined by a tachometer. The actual measured speed of elevator car with full load shall be within 5% of rated speed. The maximum difference in actual measured speeds obtained under the various conditions outlined between the "UP" and the "DOWN" directions shall be checked.

E. Post Acceptance Inspection: After the elevator is accepted by the local jurisdiction, a second inspection will be conducted (without weights) to determine specification compliance above and beyond the code requirements of the acceptance inspection.

**3.03 Reinspection:**

A. If any equipment is found to be damaged or defective, or if the performance of the elevator does not conform with the requirements of the contract specifications or the Safety Code, no approval or acceptance of elevators shall be issued until all defects have been corrected. When the repairs and adjustments have been completed and the discrepancies corrected, the Owner shall be notified and the elevator will be reinspected. Rejected elevators shall not be used until they have been reinspected and approved.

**Note to specifier: Consider a Reinspection Penalty in addition to any additional fees imposed by the AHJ for repeated inspections. Significant liquidated damages should be considered if any punch list items are not completed within one follow up inspection, the Contractor should be back charged for re-inspection.**

**3.04 ADJUSTING AND CLEANING**

- A. All equipment shall be adjusted prior to final testing and acceptance.
- B. Paint exposed work soiled or damaged during installation.

**END OF SECTION**