


Implementing a Real-Time Transit Mobile Customer Information System

Vision vs. Reality
Apr 11, 2016 → Apr 11, 2018



Hoki Tse

Engineer – Intelligent Transportation Systems



Minneapolis – St. Paul, Minnesota



2018 Fare Collection/Revenue Management
& TransTech Conferences

Key Presentation Take-Aways

- Metro Transit Overview
- ***A Line*** Arterial Bus Rapid Transit
- Project Vision and Goals
- Reality Check
- Lessons Learned
- Next Steps

Metro Transit Overview

81.9 million RIDES


264,347 AVERAGE WEEKDAY RIDERSHIP




57.3 million
RIDES



24.6 million
RIDES




907 SQ. MILES



130 ROUTES


55

URBAN LOCAL



63*

EXPRESS



9

SUBURBAN LOCAL



2
LIGHT RAIL



1
COMMUTER RAIL

* Includes Maple Grove Transit routes operated by Metro Transit

Through Dec 31, 2017

Metro Transit Bus Service



BUS



514 40-FOOT DIESEL BUSES



133 HYBRID-ELECTRIC BUSES



13 A LINE BUSES



64 COACH BUSES



185 60-FOOT ARTICULATED BUSES



189,463
AVG. WEEKDAY
BOARDINGS



24
TRANSIT CENTERS

12,067
BUS STOPS

970+
BUS SHELTERS



85%
BUS ON-TIME
PERFORMANCE



2,403,372
TOTAL VEHICLE
HOURS OF
SERVICE



7,940
AVG. VEHICLE
MILES BETWEEN
SERVICE CALL



64
PARK & RIDE LOTS/
RAMPS (BUS-ONLY)

15,674
PARK & RIDE
SPACES (BUS-ONLY)

300+
MILES OF BUS-
ONLY SHOULDER

Through Dec 31, 2017

A lot has happened since 2016 TransITech...

**Implementing a Real Time Transit
Mobile Customer Information System**

Gary Nyberg
*Metro Transit, Manager of
Technology Systems
Minneapolis/ St. Paul,
Minnesota*


2016 TransITech Conference 



**WE'VE GOT YOUR
PLAYBOOK
FOR SUPER BOWL**

Know Your Route

Use the new MetroTransit app to buy
your bus, train or Northstar ticket on
your smartphone!

 metrotransit.org/superbowl [#MetroTransitMN](https://twitter.com/MetroTransitMN)

Apr 11, 2016

San Diego, California

First Arterial BRT – *A Line*



Specialized
Vehicles



Off-Board
Payment



Enhanced
Stations



Curb
Extensions




Transit Signal
Priority





10-Minute
Frequency

A Line Arterial BRT in Numbers

- 2 LRT connections
- 4 cities
- 10 miles
- 20 stations
- 25 local bus routes connections
- 5,400 weekday rides



Vision to Alleviate Connection Anxiety



Onboard Real-Time Mobile Customer Information System (CIS)


- **Goal**

Deliver real time, relevant information to transit riders via a customer information display system mounted to the ceiling or handrail stanchion of Metro Transit buses, light rail and commuter trains.

- **Metro Transit Vision** *Toward 2020*

1. Enhance the customer experience.
2. Improve the amount and quality of information for customers.

2016 – Initial Mobile CIS Concept



2016 – Project Initiation

- ✓ • Business Case – Complete
- ✓ • Concept of Operations/Use Cases – Complete
- ✓ • RFI: Issue RFI, Review RFI/update RFP – Complete
- ✓ • Finalize Requirements - Complete
- ✓ • Advertise RFP - 3/23/16 - 4/27/16
- ! • Evaluate Proposals - 4/27/16 - 5/31/16

Lots of Clarifications

Evaluation Completed Jul 2016



2016 – Getting Closer to Pilot Deployment



- Award Contract – 5/31/16
- Issue limited NTP for Pilot Install – Early June
- Proof of Concept Testing – Late June
- Issue second NTP for remaining buses – Early July
- Installation on remaining 11 buses – Late July/
August
- Final Acceptance - September




Not as Easy as You Think...


| Milestone | Vision | Reality |
|--|-----------------------|----------|
| Award Contract | May 2016 | Feb 2017 |
| On Site Kickoff & <i>A Line</i> bus tour with Vendor | + | May 2017 |
| Final Design Review | + | Dec 2017 |
| NTP and Pilot Install | Early Jun 2016 | Jan 2018 |
| Issue second NTP for remaining 12 buses | Early Jul 2016 | Feb 2018 |
| Install on remaining buses | Late Jul/ Aug 2016 | Apr 2018 |

What happened here?

Initial Communication Flow




Deployed Communication Flow




May 2017 – Kickoff Meeting

- Started with “Single-wide” hanging screens
- Vendor suggested “Double-wide” screen similar to NYC MTA
- Wider & heavier
- Redesign & re-evaluated risks
 - Make sure new screens don’t fall or hit riders
- +4 months confirming with Gillig
 - Not voiding warranties



Oct 2017 – Change Order

- More **information** available on 2x wider screens
- Lead to more **successful** project outcome & impact



May 2017 – User Content Mockups with Single-wide Horizontal Screens

This Stop

Snelling & Hoyt/Nebraska

UPCOMING STOPS / TRANSFER TO

- Snelling & Como 3
- Snelling & Hewitt
- Snelling & Minnehaha 67
- Snelling & University 16, 21
- Snelling & Dayton 21, 53

NexTrip 10:38 AM

No connecting service

Next Stop

Snelling & Como

UPCOMING STOPS / TRANSFER TO

- Snelling & Hewitt
- Snelling & Minnehaha 67
- Snelling & University 16, 21
- Snelling & Dayton 21, 53
- Snelling & Grand 63

NexTrip 4:42 PM

Trips departing

COMO AVE & SNELLING AVE EASTBOUND

| ROUTE | DESTINATION | DEPARTS |
|-------|------------------|---------|
| 3B | to Dwtn St. Paul | 12 min |
| 3A | to Dwtn St. Paul | 5:12 |

WESTBOUND

| ROUTE | DESTINATION | DEPARTS |
|-------|--------------|---------|
| 3B | to Dwtn Mpls | 2 min |
| 3B | to Dwtn Mpls | 5:06 |

SNELLING AV & COMO STATION EASTBOUND

| ROUTE | DESTINATION | DEPARTS |
|--------|------------------|---------|
| A Line | to 46 ST Station | 4 min |
| 3B | to Dwtn St. Paul | 9 min |

Real Time Scheduled

Next Stop

Snelling & Como

UPCOMING STOPS / TRANSFER TO

- Snelling & Hewitt
- Snelling & Minnehaha 67
- Snelling & University 16, 21
- Snelling & Dayton 21, 53
- Snelling & Grand 63

Transfer to: 3A, 3B, 84

Next Stop

Snelling & Como

UPCOMING STOPS / TRANSFER TO

- Snelling & Hewitt
- Snelling & Minnehaha 67
- Snelling & University 16, 21
- Snelling & Dayton 21, 53
- Snelling & Grand 63

RIDER ALERT






Effective Saturday, July 4, at 4:00 AM Snelling & Como will be closed for maintenance.

Aug 2017 – User Content Final Design with Double-wide Horizontal + Vertical Screens

Next Stop

Snelling & Como

UPCOMING STOPS / TRANSFER TO

- Snelling & Hewitt
- Snelling & Minnehaha  67
- Snelling & University   16, 21
- Snelling & Dayton  21, 53
- Snelling & Grand  63

NexTrip

4:42 PM

Trips departing

COMO AVE & SNELLING AVE
EASTBOUND

| ROUTE | DESTINATION | DEPARTS |
|-------|------------------|---------|
| 3B | to Dwtn St. Paul | 12 min |
| 3A | to Dwtn St. Paul | 5:12 |

WESTBOUND

| ROUTE | DESTINATION | DEPARTS |
|-------|--------------|---------|
| 3B | to Dwtn Mpls | 2 min |
| 3B | to Dwtn Mpls | 5:06 |

SNELLING AV & COMO STATION
EASTBOUND

| ROUTE | DESTINATION | DEPARTS |
|--------|------------------|---------|
| A Line | to 46 ST Station | 4 min |
| 3B | to Dwtn St. Paul | 9 min |

• Real Time • Scheduled

NEXT STOP

Snelling & Como

UPCOMING STOPS

- Snelling & Hewitt
- Snelling & Minnehaha



NexTrip

1:41 PM

| ROUTE | DESTINATION | DEPARTS |
|-------|---------------|---------|
| 3B | Dwtn St. Paul | 19 min |
| 3A | Dwtn St. Paul | 2:11 |
| 3B | Dwtn Mpls | 4 Min |
| 3A | Dwtn Mpls | 2:06 |

• Real Time • Scheduled

STOP REQUESTED

Snelling & University
  Route(s) 16, 21, 84

UPCOMING STOPS

- Snelling & Dayton
- Snelling & Grand
- Snelling & St. Clair
- Snelling & Randolph
- Snelling & Highland
- Snelling & Fairview
- Ford & Fairview
- Ford & Kenneth
- Ford & Finn
- Ford & Woodlawn
- 46th St & 46th Ave


Screen Placement

- Ensure screens are high enough for 7-footers




Wiring Challenges


- Ensure proper wiring amid current equipment
- Outlets, Communications, Interference




Jan 2018 – First Run



- 1 of 13 **A Line** buses
- Transfer connection files not available during first run



Mar 2018 – Third Run



NEXT STOP
Snelling & University
Route(s) 16, 21, 84


NexTrip 10:22 AM

| ROUTE | DESTINATION | DEPARTS |
|-------|---------------------------------|---------|
| 16 | University Ave SE & 27th Ave SE | 2 Min |
| 21 | Uptown Station & Terminal | 13 Min |

• Real Time • Scheduled

UPCOMING STOPS

- SNELLING & DAYTON STATION
- SNELLING & GRAND STATION
- SNELLING & ST CLAIR STATION
- SNELLING & RANDOLPH STATION
- SNELLING & HIGHLAND STATION
- FORD & FAIRVIEW STATION
- FORD & KENNETH STATION
- FORD & FINN STATION



NEXT STOP
Snelling & University

UPCOMING STOPS

- SNELLING & DAYTON
- SNELLING & GRAND

Connect here to:
Route(s) 16, 21, 84
METRO Green Line

- Successful testing during February and March on pilot bus
- Installation on remaining 12 buses in April (right now)
- Feedback by survey or email to Customer Relations

Lessons Learned

- From 2016:
 - Procurement process will take longer than you think
 - Do not over define requirements
 - Allow flexibility in varied vendor solutions
- Partnerships across departments
 - More than a technology project
 - Bus Maintenance, Bus Operations, Customer Relations, Creative Services, Risk, Safety...
- Vandalism monitoring for all 13 buses

Next Step – Phase 2

- Evaluate Survey Results
 - User contents (interface, accuracy, alerts, detours...)
 - Impacts on Operators' duties
- Get ready for round 2 with a variety of bus type, model, manufacturer, etc.





Bus Operations – Technology Systems

Manager: Gary Nyberg – Gary.Nyberg@metrotransit.org

PM: Rick Paulson – Richard.Paulson@metrotransit.org

A Line Rider: Hoki Tse – Hoki.Tse@metrotransit.org